

DEMONSTRATION / NETWORK ROLLOUT & HANDOVER PACK

Plan the delivery around acceptance

Scenario: a fictional three-building office needs a segmented wired/wireless network and voice service. This is an illustrative design, not Harvestfield's production topology or configuration.

Conceptual design

Two internet providers > approved edge/firewall design > core switching > access switches by building > corporate devices, wireless access and voice endpoints. Separate corporate, guest, voice and management traffic according to approved requirements. Redundancy at one layer does not remove all single points of failure.

Illustrative delivery plan

Stage	Deliverable	Acceptance gate
Discover	Survey, requirements, constraints, service dependencies	Business owner approves scope
Design	Topology, segmentation, bill of quantities, change plan	Technical review and purchasing approval
Prepare	Staging, labelled cabling, configuration backups	Readiness check; access and power confirmed
Implement	Agreed cutover and device configuration	Connectivity/security test set passes
Handover	Inventory, support guide, backups and training	Operations owner accepts; exceptions assigned

Dependencies and risks

1. Construction works can damage cabling: agree contractor sequencing, protected routes, inspection points and reporting ownership.
2. Power or uplink failure can interrupt service: document the resilience boundary and test only the failover features included in the approved design.
3. Late equipment can affect milestones: track delivery commitments and identify approved alternatives before changing the design.
4. Voice and guest traffic need defined access rules: validate the required paths instead of assuming every VLAN should reach every other VLAN.

Change rule

Document scope, affected users, maintenance window, approvals, current backups, validation steps and rollback trigger before the cutover. Freeze unrelated changes during acceptance testing.

Synthetic scenario. Prepared with AI assistance for this portfolio; not a client record.

DEMONSTRATION / NETWORK ROLLOUT & HANDOVER PACK

Prove it works, then transfer ownership

All values and test states below are fictional. The table is an example acceptance register, not measured results from a client network.

Acceptance register

Test	Expected result	Evidence to capture
Corporate connectivity	Approved resources reachable	Test device, location and result
Guest isolation	Guest cannot reach internal resources	Denied path and approved internet test
Voice	Calls complete across required routes	Call test and observed quality
Coverage	Agreed work areas meet requirements	Survey notes and measurements
Provider failover	Recovery meets agreed criteria	Failure/recovery timing and limitations
Recovery	Approved configuration can be restored	Controlled restore-test record

Handover checklist

1. Inventory: device roles, ownership, support entitlement, locations and labelling; keep management addresses restricted.
2. Configuration: approved baseline, backup location, version/change history and recovery procedure.
3. Operations: monitoring responsibilities, escalation contacts, support windows and maintenance ownership.
4. Access: transfer privileged credentials through the approved secret-management system, not this document.
5. Acceptance: signed test record, outstanding defects, agreed exceptions, warranty/support arrangements and operations-owner sign-off.

Rollback trigger

If a business-critical connectivity or security test fails and cannot be corrected within the agreed window, revert to the approved previous state where technically feasible. Notify the change owner, preserve the test evidence and agree the next attempt.

Handover summary

"The agreed test set has been reviewed with the operations owner. Any unresolved defects are recorded with an owner and due date. Support documentation and configuration backups have been transferred through approved channels."

Synthetic scenario. Prepared with AI assistance for this portfolio; not a client record.